

000396

FEB 17 1985

11


DRAFT TECHNICAL REPORT NO. 11

PHASE 2 STAGE 2C
SELECTION OF PREFERRED SITE

HERITAGE FEATURES ASSESSMENT

THE LANDPLAN COLLABORATIVE LTD.

URBAN DOCUMENTATION CENTRE
RESEARCH UNIT FOR URBAN STUDIES
McMASTER UNIVERSITY
HAMILTON, ONTARIO



ENVIRONMENTAL
ASSESSMENT
LANDFILL COMPONENT OF
SOLID WASTE MANAGEMENT

JANUARY 1985

TABLE OF CONTENTS

		<u>Page</u>
1.0	TERMS OF REFERENCE	1-1
2.0	CURRENT CONDITIONS	2-1
	2.1 Study Procedure	
	2.2 Study Assumptions	
	2.3 Findings	
3.0	SIGNIFICANCE	3-1
4.0	EVALUATION/EFFECT ON HERITAGE FEATURES	4-1
5.0	COMPARISON OF HERITAGE FEATURES IMPACTS	5-1
	5.1 Number of Significant Heritage Features Impacted	
	5.2 Number of Heritage Features Impacted	
	5.3 Ranking the Sites on Impacts	
6.0	MITIGATION	6-1
	6.1 General	
	6.2 Options for Mitigation - Six Candidate Sites	
	6.3 Conclusions	
7.0	CONCLUSIONS/RECOMMENDATION	7-1

	<u>Following Page</u>
--	---------------------------

LIST OF ILLUSTRATIONS

Maps

1. Inventory of Heritage Features for Site Plan Area A, B, C	5-1
2. Inventory of Heritage Features for Site Plan Area D, and C	5-1

APPENDICES

Appendix

- A. Documentation Reviewed
- B. Inventory Sheets
- C. Correspondence with LACACS

URBAN DOCUMENTATION CENTRE
 RESEARCH UNIT FOR URBAN STUDIES
 McMASTER UNIVERSITY
 HAMILTON, ONTARIO

1.0 TERMS OF REFERENCE

The terms of reference for the heritage features assessment were as follows:

1. Site visits to confirm the locations of heritage features identified in Stage 2B, and to identify any further heritage features.
2. Each feature will be investigated and evaluated with respect to its particular characteristics and its significance at the local and/or regional level.
3. The extent of any conflict between heritage features and the implementation of sanitary landfilling on the Candidate Sites will be evaluated, and recommendations with respect to mitigation measures will be made where appropriate.
4. Assistance will be sought from Local Architectural Conservation Advisory Committees and municipal officials in determining the significance of heritage features, and in consideration of mitigation measures.

2.0 CURRENT CONDITIONS

2.1 Study Procedure

The consultants accomplished the following tasks in producing this study:

- a. Reviewed all existing documentation (see Appendix A).
- b. Viewed all heritage features on each of the six Candidate Sites in the field and in particular, those features within the Site Plan Areas.
- c. Contacted the Ministry of Citizenship and Culture (Mr. David Cuming) for guidance and inventory information.
- d. Contacted the Local Architectural Conservation Advisory Committees (LACACS) and historical societies in the area municipalities (see Appendix C) for inventory information and significance of heritage features.
- e. Photographed and recorded, on "inventory sheets" (see Appendix B), all heritage features located on each of the six Candidate Sites.
- f. Located each of the heritage features on Ontario Base Maps at a scale of 1:10,000.
- g. Rated significance of each of the heritage features.
- h. Evaluated the effect of landfilling on each of the heritage features.
- i. Proposed general mitigation measures.
- j. Recommended site locations based upon heritage features considerations.

2.2 Study Assumptions

To determine the impact on heritage features of any given landfill site, some assumptions on the degree of development that will take place due to landfilling were made. In conjunction with the project co-ordinator, Walker Wright Young Associates Limited and Hydrology Consultants, the following assumptions were made:

1. Each site has a setback of 100 metres (328 feet) to the toe of the slope.
2. The landfill height does not exceed 15 m (49 feet).
3. The slope of the edge of the landfill is a ratio of 4 horizontal to 1 vertical.
4. Based on points 2. and 3. above, the landfill would reach its maximum height of 160 m from the boundary of each site.
5. Specific areas within the Candidate Sites have been identified for landfilling. For purposes of the heritage features assessment, it was assumed that the Site Plan Area of each Candidate Site, within the setback, would be subject to landfilling.
6. Impacts of a visual nature were not considered in this evaluation. Visual impacts have been documented in the "Visual Assessment" report prepared by The Landplan Collaborative Ltd.

2.3 Findings

Through the review of existing documentation of the heritage features and the field work, the consultants recorded the following number of heritage features located on each of the six Candidate Sites:

Site A	11 heritage features
Site B	9 heritage features
Site C	17 heritage features
Site D	1 heritage feature
Site E	6 heritage features
Site F	0 heritage features

Features considered as "heritage" for this study included historic buildings, landscapes and site features. Archaeological resources were not considered in this study. Each of the Candidate Sites exhibits particular characteristics which make up the "cultural landscape". Cultural landscapes are defined in the "Guidelines on the Man-Made Heritage Component of Environmental Assessments" (Ministry of Citizenship and Culture) as any discrete aggregation of man-made features which has one or more of the following attributes:

- . it is the only one of its kind or one of the remaining few.
- . it is the most outstanding example of its kind.
- . it is perceived by the moving eye as a built-up area with a particularly interesting and attention-catching series of visions.
- . it provides the observer with a strong and definite sense of position or place.
- . it has a unique or typical material content well executed in terms of colour, texture, style and scale.
- . it is exemplary of distinctive cultural processes in the historic development and use of land.
- . it is part of a complex of outstanding scenic/historic areas or is perceived as an ensemble of different landscape categories such as townscape/agricultural landscape/natural landscape/waterscape.
- . it is part of a network of landscape categories as mentioned above, and presents to the moving eye opportunities for special sequential experiences or a series of visions of distinctive scenic views.

Heritage features of this region of southern Ontario include many buildings, landscapes, and site features of a very diverse nature. Some are of national or provincial significance while others are of local significance. None of the heritage features located on the Candidate Site areas

is considered to be nationally or provincially significant. Some are locally significant. The region contains a large number of locally significant heritage features, many of which are farm-related (i.e., residences, barns, outbuildings, and landscapes). The potentially affected locally significant heritage features from the candidate site areas are a very small sample of the features of the immediate environs and region.

The descriptions of each of the cultural landscapes of each of the Candidate Sites are:

Site A - The site is rural and mainly agricultural in character. Numerous rural residential dwellings are located on the southern boundary. A hydro transmission corridor runs east and west through the site and a transformer station is located just north of the site. Site A is visually flat and has been extensively modified to permit large-scale agricultural operations and rural residential uses in recent years. Few heritage features other than farm buildings and associated farmstead plantings remain.

Site B - Similar in character to Site A, this site is rural and mainly agricultural in nature, although there is a greater number of residential units with the greatest density on the north, east and south sides. The site is visually flat with few heritage features other than farm buildings and associated farmstead plantings remaining.

Site C - Similar in character to Sites A and B, this site is rural and mainly agricultural in nature. A number of residences are located along Trafalgar and Burnhamthorpe Roads. The site is visually flat with few heritage features other than farm buildings and associated farmstead plantings remaining.

Site D - The site is rural and agricultural in nature, is very flat visually, with few heritage features and no semblance of original agricultural field patterns, fences, or other accoutrements.

Site E - This site is also agricultural and rural in character and is similar, from a heritage viewpoint, to Site D.

Site F - No heritage features were recorded on this site. It is the most "natural" in character of all the sites.

None of the cultural landscapes are considered to be historic landscapes. Each has been greatly modified in the recent past and, although most contain a number of heritage features, they are typical of modern rural and agricultural landscapes and do not represent historic rural or agricultural landscapes other than the original and typical gridiron pattern of settlement and land survey.



3.0 SIGNIFICANCE

Each of the heritage features identified has been rated as to its significance at the local and/or regional level. The significance of each heritage feature is based upon the following criteria, which are included in the "Guidelines on the Man-Made Heritage Component of Environmental Assessments" (Ministry of Citizenship and Culture):

- . It is associated with a well-known event.
- . It is associated with a well-known person or group.
- . It is associated with the first or formative aspect of activity.
- . It is associated with activity or endeavour of relative antiquity.
- . It is associated with activity of substantial duration.
- . It is associated with an activity or endeavour that affected a substantial population or geographic area.
- . It is a representative work of a generally recognized surveyor, architect, engineer, master builder or craftsman.
- . It has a group value, especially as an example of town planning (eg: squares, terraces or model villages).
- . It has been well executed within the conventions of a recognized period style or method of construction.
- . It is a technological innovation or adaptation or represents engineering virtuosity.
- . It is a good, typical example of an early style or construction technique or of an early structure or device commonly used for a specific purpose throughout an area or period.
- . It has an unusual or unique style or construction technique.
- . It is the first or earliest of a surviving specimen of a type.
- . It is the last or latest surviving specimen of a type.
- . It is the only example of a particular type or one of the remaining few.
- . It is a landmark in a streetscape, townscape or countryside setting.
- . It contributes to the harmony of its neighbourhood.

The following chart summarizes the descriptions and significance of each identified heritage feature recorded for the Candidate Sites. Relative significance of heritage features is derived from the criteria outlined above. Features considered to be of high significance satisfy at least one of the criteria and usually more than one. Low significance heritage features satisfy only partially, or not at all, any of the criteria.

Candidate Site	Map Ref	Name and Location of Feature	Description	Significance High, Low
A	A7	4076 Ninth Line residence	1-1/2 storey salt box house 1868	High
*A	A5	1265 Burnhamthorpe Road E., farm residence	1-1/2 storey frame greatly modified	Low
*A	A3	1141 Burnhamthorpe Road E., farm residence	1-1/2 storey frame, centre gable, 1868	Low
*A	A3	1141 Burnhamthorpe Road E., outbuildings	unique outbuilding complex & pond	High
A	A2	1053 Burnhamthorpe Road E., farm residence	1-1/2 storey brick 1848 greatly modified	Low
A	A6	1481 Burnhamthorpe Road E., residence	1-1/2 storey frame 1848 porch & trelliage	High
A	A6	1481 Burnhamthorpe Road E., farmstead plantings	remnants of early plantings	High
A	A1	489 Burnhamthorpe Road E., residence	Regency cottage 1847 original porch. OHS plaque	High
A	A1	489 Burnhamthorpe Road E., barns	2 original barns	High

A	A1	489 Burnhamthorpe Road E., farmstead	remnants of early plantings with recent additions	High
*A	A4	1189 Burnhamthorpe Road E., residence	farm house 1862 extensive renovations	Low
A	A6	1481 Burnhamthorpe Road E., residence	1-1/2 storey frame 1848 porch & trelliage	High
A	A6	1481 Burnhamthorpe Road E., farmstead plantings	remnants of early plantings	High
A	A1	489 Burnhamthorpe Road E., residence	Regency cottage 1847 original porch. OHS plaque	High
A	A1	489 Burnhamthorpe Road E., barns	2 original barns	High
A	A1	489 Burnhamthorpe Road E., farmstead	remnants of early plantings with recent additions	High
*A	A4	1189 Burnhamthorpe Road E., residence	farm house 1862 extensive renovations	Low
*B	B3	3444 Trafalgar Rd. farm residence	1-1/2 storey stone, stuccoed, c. 1867	High
*B	B3	3444 Trafalgar Rd. farmstead plantings	remnant plantings	Low
B	B6	257 Dundas St. E. farm residence	1-1/2 storey brick stuccoed, 1850's	High
B	B6	257 Dundas St. E. farmstead plantings	remnant plantings	High
*B	B4	3558 Trafalgar Rd. residence	c. 1900 barn converted to residence-block and frame	Low
*B	B5	3369 Sixth Line farm residence	1-1/2 storey c. 1862 poly-chrome brick	High

*B	B5	3369 Sixth Line farmstead plantings	remnant plantings c. 1920	Low
B	B2	3040 Trafalgar Rd. residence	1-1/2 storey c. 1834 stucco with cobblestone accents	High
B	B1	3048 Trafalgar Rd. residence	2-1/2 storey veterinary office and residence clapboard, c. 1900	High
B	B1	3048 Trafalgar Rd. landscape plantings	remnant landscape plantings c. 1900	High
C	C7	1086 Burnhamthorpe Rd. E. residence	frame school 1874 renovated for residence	Low
C	C4	1086 Burnhamthorpe Rd. E. farm residence	brick Palladian plan 1839. original portion 1824 made with English brick	High
C	C4	1086 Burnhamthorpe Road E. gardens	remnants of 1840's "English" garden	High
C	C8	3480 Ninth Line residence	1-1/2 storey red brick Victorian 1886	High
C	C8	3480 Ninth Line farmstead planting	remnant plantings	Low
C	C8	3480 Ninth Line outbuildings	barns and barnyard	Low
C	C6	1264 Burnhamthorpe Road E., residence	1-1/2 storey frame Gothic style c. 1850's	Low
C	C6	1264 Burnhamthorpe Road E., farmstead plantings	remnant plantings	High
C	C5	1158 Burnhamthorpe Road E., residence	1-1/2 storey brick 1886 with additions	High
C	C5	1158 Burnhamthorpe Road E., outbuildings	original barns	High

C	C5	1158 Burnhamthorpe Road E., farmstead plantings	remnant laneway plantings	High
*C	C3	3555 Trafalgar Road residence	1-1/2 storey c. 1868 stucco over frame much altered	Low
*C	C2	3437 Trafalgar Road residence	4-1/2 storey c. 1877 stucco over wood	High
*C	C2	3437 Trafalgar Road barns/outbuildings	original barn	High
*C	C2	3437 Trafalgar Road farmstead plantings	remnants of plantings	High
*C	C1	3371 Trafalgar Road residence	1-1/2 storey clapboard over frame house	High
*C	C1	3371 Trafalgar Road farmstead plantings	remnants of plantings	High
D	D1	Bronte Road, 1st Line Milton, M.G. 935142 farm residence	c. 1830's frame house	High
*D	D2	5357 Bronte Road, Milton, farm residence	1-1/2 storey stucco Ontario Gothic	High
*D	D2	5357 Bronte Road, Milton, farmstead plantings	remnant plantings orchard	High
*D	D2	5357 Bronte Road, Milton, barns	original barns	High
E	E3	Bell School Line, Milton, M.G. 915122 farm residence	Victorian 2 storey brick, c. 1890's	High
E	E3	Bell School Line, Milton, M.G. 915122 farmstead plantings	remnant plantings c. 1900	High
E	E4	Tremaine Road, Milton M.G. 909145 farm residence	2 storey brick c. 1900	High

E	E4	Tremaine Road, Milton M.G. 909145 farmstead plantings	remnant plantings c. 1900	High
E	E2	Tremaine Road, Milton M.G. 921133 farm residence	2 storey c. 1870 brick	High
*E	E1	Tremaine Road, Milton M.G. 913141 farm residence	1-1/2 storey, 5 bay stucco	High

* Heritage feature located within "Site Plan Area".

4.0 EVALUATION/EFFECT ON HERITAGE FEATURES

For purposes of impact evaluation, the consultants have assumed that all heritage features which required habitation or resident maintenance for their preservation will be impacted as they must be removed or relocated.

Impacts considered are limited to:

1. destruction or partial removal of a heritage feature.
2. isolation of a heritage feature from a surrounding historic environment.

As noted above (Paragraph 2.3), none of the heritage features are situated in an historic landscape consistent with the heritage significance of the features themselves. The larger settings are much more modern in character than the features. Where the immediate environs were considered to be of an historic nature, these environs were noted as a heritage feature and their significance was rated.

In summary, each of the heritage features identified within the Site Plan Areas is impacted by the landfilling proposal in that they will not be inhabited or utilized for their existing functions after the landfill proposals are implemented. A comparison of impacts is given in the next section (5.0) and mitigation measures to lessen impacts are given in Section 6.0.

5.0 COMPARISON OF HERITAGE FEATURE IMPACTS

The number of heritage features impacted are those located within the Site Plan Areas as indicated on Maps for sites A, B, C, D and E.

5.1 Numbers of Significant Heritage Features Impacted

Site A	1
Site B	2
Site C	5
Site D	3
Site E	1
Site F	0

5.2 Numbers of Heritage Features Impacted (includes significant features)

Site A	4
Site B	5
Site C	6
Site D	3
Site E	1
Site F	0

5.3 Ranking the Sites on Impacts

Five significant heritage features will be impacted on Site Plan Area C. Six heritage features (including five significant heritage features) will be impacted on Site Plan Area C. Site Plan Area C heritage features are quantitatively and qualitatively the most affected, followed closely by heritage features of Sites B and D. One heritage feature is impacted on Site E and no heritage features exist on Site F.





MAP 1


LEGEND

- ◇ Heritage Features
Inventory Reference #
- Candidate Site
- Site Plan Area

Map Information Compiled By:
The Landplan Collaborative Ltd


PHASE 2, STAGE 2C SELECTION OF PREFERRED SITE

ENVIRONMENTAL ASSESSMENT OF THE LANDFILL COMPONENT OF HALTON'S SOLID WASTE MANAGEMENT SYSTEM



Walker Wright Young
Associates Limited





MAP 2

LEGEND

◇ Heritage Features
Inventory Reference


— Candidate Site

— Site Plan Area

Map Information Compiled By:
The Landplan Collaborative Ltd.

PHASE 2, STAGE 2C SELECTION OF PREFERRED SITE

ENVIRONMENTAL ASSESSMENT OF THE LANDFILL COMPONENT OF HALTON'S SOLID WASTE MANAGEMENT SYSTEM



Walker Wright Young
Associates Limited

6.0 MITIGATION

6.1 General

The options for mitigation would appear to be two-fold in nature, depending upon the number of heritage features potentially impacted. The two mitigative options are:

1. Move the heritage feature(s) to another location. Because none of the settings (cultural landscapes) contribute greatly to the heritage features, the relocation of these features to a similar setting would not adversely affect their value as a heritage feature. The exceptions to this statement are where a heritage feature has been assessed as significant, partly or mainly because of its association with a particular geographic location. This factor has been noted in Section 3.0.
2. Modify the proposed landfill to accommodate the heritage features.

6.2 Options for Mitigation

The six Site Plan Areas were compared based upon the following assumptions:

1. The area of each Candidate Site to be developed is approximately 110121 ha in size. The landfill is 15 m high and has a capacity of 11.3 million cubic yards. Each Site Plan Area is significantly smaller than the Candidate Site areas, with the exception of Site F which remains the same.
2. Relocation of a large number of heritage features is not feasible due to the potential lack of sites for relocation.
3. Relocation of some heritage features such as mature farmstead planting is impossible. Relocation of some heritage features, such as out-

buildings, may be difficult, or impossible, due to the nature of construction, age and state of deterioration of some of these structures.

Based upon these considerations, the options for mitigation for each site are:

Site Plan Area A

1. Based on its size, locating the landfill away from heritage features may be possible.

Site Plan Area B

1. Because of the site's relatively small size, there is little opportunity to modify the landfill.
2. Relocation of the significant heritage features is possible, but difficult due to their construction and age.

Site Plan Area C

1. This site is large enough to provide some options in landfill location away from the heritage features.

Site Plan Area D

1. There are few options for modifying the landfill due to the site's relatively small size.
2. The significant heritage features could be relocated with the exception of the landscape plantings. Re-creation of the entire complex of features is not possible.

Site Plan Area E

1. Some opportunity exists to modify the landfill within Site E to avoid heritage features.

Site Plan Area F

1. No heritage features have been recorded on Site F.

6.3 Conclusions

Options for mitigation for each of the six Site Plan Areas from highest to lowest are:

Site F (no heritage features recorded)
Site A
Site E
Site B
Site D
Site C



7.0 CONCLUSIONS/RECOMMENDATIONS

The following chart summarizes the evaluation and provides the basis for a recommendation.

<u>Factors</u>	<u>Site Plan Areas</u>					
	A	B	C	D	E	F
No. of Significant Heritage Features	1	2	5	3	1	0
No. of Heritage Features	4	5	6	3	1	0
Mitigation by Relocation	L	L	L	M	M	N/A*
Mitigation by Relocation of Landfill	H	L	H	L	M	N/A*

*N/A - not applicable
 L - low potential
 M - medium potential
 H - high potential

The recommended ranking of site locations for the proposed landfilling operation based upon heritage features considerations is in order of preference:

1. Site F
2. Site A
3. Site E
4. Site B
5. Site D
6. Site C

APPENDIX A

DOCUMENTATION REVIEWED

Walker Wright Young Associates Limited, Consultants. Interim Report on Public Concerns and Issues, Phase 2, Stage 2C. Selection of Preferred Site, June 1984.

Ibid, Selection of Preferred Site, Phase 2, Stage 2C, Final Work Program, May 1984.

Ibid, Analysis of Submission, Phase 2, Stage 2C, Final Site(s) Evaluation, April, 1984.

Ibid, Consolidation Report, Phase 2, Stage 2B, Selection of Candidate Sites, April 1984.

Ibid, Draft Report, Phase 2, Stage 2B, Selection of Candidate Sites, February, 1984.

Ibid, Appendices, Phase 2, Stage 2B, Selection of Candidate Sites, February, 1984.

Ibid, Submission Evaluation Factors, Phase 2, Stage 2B, Selection of Candidate Sites, January, 1984.

Ibid, Final Evaluation Factors, Phase 2, Stage 2B, Selection of Candidate Sites, January, 1984.

Ibid, Submission, Phase 2, Stage 2A, General Overview Analysis, October, 1983.

Regional Municipality of Halton, Halton Heritage Study, Volumes I, II and III. October, 1981.

Concerned Residents Over Waste, The Social and Cultural Impact Committee. Social and Cultural Impact Study, May, 1984.


Niagara Escarpment Commission, Heritage Resources Study, The Niagara Escarpment, 1978.



Ministry of Culture and Recreation (Citizenship and Culture). Guidelines on the Man-Made Heritage Component of Environmental Assessments, September, 1980.



APPENDIX B


INVENTORY SHEETS





NAME : Regency Cottage		REFERENCE NO : A-1	
NATURE OF FEATURE : House		DATE OF REPORT : November, 1984	
		THEME CATEGORY : S - European	
LOCATION	ADDRESS : 489 Burnhamthorpe East, Oakville		
	LOT 12	CON 2 NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/12		
	MILITARY GRID REF. 023176		
	AIR PHOTO REF.		
DATING : 1847			
ORIGINAL USE : Farm House			
CURRENT USE : Residential			
OWNERSHIP : Private			
PROTECTION STATUS : 2, 4			
DESCRIPTION : - Built in 1847 - Red brick regency cottage in good condition - Original porch roof - Two original barns on the property - Oakville Historical Society plaque - Remnants of early farmstead plantings with recent additions			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS - Oakville Historical Society - Ontario Inventory of Buildings - Social & Cultural Impact Study, May, 1984	
		PRESENT OWNER Don & Gloria Marshall	



NAME : House		REFERENCE NO : A-2	
NATURE OF FEATURE : Farm House		DATE OF REPORT: November, 1984	
		THEME CATEGORY: S. European	
LOCATION	ADDRESS : 1053 Burnhamthorpe Road, R.R.#1, Oakville, Ont. L6J 4Z2		
	LOT Pt. 10	CON 2 NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/12		
	MILITARY GRID REF 026179		
	AIR PHOTO REF.		
DATING : 1848			
ORIGINAL USE : Farm House			
CURRENT USE : Farm House			
OWNERSHIP : Private			
PROTECTION STATUS: 2 & 4			
DESCRIPTION : - Built in 1848 - Original 1½ story gable of white clapboard - Has been recently moved, sided and modified by the addition of gables, etc.			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS	
		Oakville Heritage Community Study.	
		Inventory 1976, 1981	
		Social & Cultural Impact Study, May, 1984	
		PRESENT OWNER	
		Gail & Rick Redshaw	


NAME : House		REFERENCE NO : A.3	
NATURE OF FEATURE :		DATE OF REPORT : November 1984	
Farm House		THEME CATEGORY :	
LOCATION	ADDRESS : 1141 Burnhamthorpe Road, R.R#1, Oakville, Ont. L6J 4Z2		
	LOT 9	CON 2 NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/12		
	MILITARY GRID REF. 028182		
	AIR PHOTO REF.		
DATING : 1868			
ORIGINAL USE : Farm House			
CURRENT USE : Farm House			
OWNERSHIP : Private			
PROTECTION STATUS : 2 & 4			
DESCRIPTION : - Built in 1868 - 1½ storey, centre gable, Ontario Gothic - Unique outbuilding complex and pond			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social & Cultural Impact Study, 1984	
		PRESENT OWNER Victor Fox	


NAME : House		REFERENCE N° : A-4	
NATURE OF FEATURE :		DATE OF REPORT : November, 1984	
House		THEME CATEGORY :	
LOCATION	ADDRESS : 1187 Burnhamthorpe Road, RR #1, Oakville, Ontario L6J 4Z2		
	LOT 9	CON 2 NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/12		
	MILITARY GRID REF. 029183		
	AIR PHOTO REF.		
DATING : 1862			
ORIGINAL USE : Farm House			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 4			
DESCRIPTION : - Built in 1862 - Extensive renovation to exterior facade			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social & Cultural Impact Study/ May, 1984	
		PRESENT OWNER Ivo Jolic	

NAME : House		REFERENCE NO : A-5	
NATURE OF FEATURE :		DATE OF REPORT: November, 1984	
House		THEME CATEGORY:	
LOCATION	ADDRESS : 1265 Burnhamthorpe Road, R.R. #4, Oakville, Ontario.		
	LOT 8	CON 2 NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/12		
	MILITARY GRID REF. 031186		
	AIR PHOTO REF.		
DATING : 1848			
ORIGINAL USE : Farm House			
CURRENT USE : Farm House			
OWNERSHIP : Private			
PROTECTION STATUS: 2 & 4			
DESCRIPTION : - 1½ storey Gable house. - Sided with white clapboard. - Extensive outside modification.			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social & Cultural Impact Study/May 1984	
		PRESENT OWNER Heinrich & Gertrude Schultz	


NAME : House		REFERENCE NO : A.6	
NATURE OF FEATURE : House		DATE OF REPORT : November 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 1481 Burnhamthorpe Rd. E., RR#1, Oakville, Ontario		
	LOT 6	CON	2NDS
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30M/12		
	MILITARY GRID REF. 035193		
	AIR PHOTO REF.		
			
DATING : 1848			
ORIGINAL USE : Farm House			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 4			
DESCRIPTION : - 1½ storey frame - Original trelliage - Remnants of early farmstead plantings			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social & Cultural Impact Study, May 1984 Town of Oakville, LACAC	
		PRESENT OWNER	

NAME : Farm		REFERENCE NO : A.7	
NATURE OF FEATURE : House		DATE OF REPORT : November, 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 4076 Ninth Line, R.R. #1, Oakville, Ontario. L6J 1Z2		
	LOT 6	CON 2 NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30N/12		
	MILITARY GRID REF. 035195		
	AIR PHOTO REF.		
DATING : 1868			
ORIGINAL USE : Farm House			
CURRENT USE : Residential			
OWNERSHIP :			
PROTECTION STATUS : 4			
DESCRIPTION : White clapboard, 1½ storey salt box house built by Joseph Snider, 1868			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social & Cultural Impact Study, May 1984	
		PRESENT OWNER	



NAME : Residence		REFERENCE NO : B.1	
NATURE OF FEATURE : Residence		DATE OF REPORT : November 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 3048 Trafalgar Road, Oakville, Ontario		
	LOT 13	CON 1 NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/5		
	MILITARY GRID REF. 034156		
	AIR PHOTO REF.		
			
DATING : c. 1900			
ORIGINAL USE : Veterinary Office & Residence			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 4			
DESCRIPTION : 2½ storey hip-roofed Victorian house clapboard construction remnant landscape plantings, c. 1900			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social and Cultural Impact Study, May 1984 Town of Oakville LACAC	
		PRESENT OWNER Harvey & Mary Christie	

NAME : Residence		REFERENCE NO : B.2	
NATURE OF FEATURE : Residence		DATE OF REPORT : November 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 3040 Trafalgar Road, Oakville, Ontario		
	LOT 13	CON 1 NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/5		
	MILITARY GRID REF. 034156		
	AIR PHOTO REF.		
DATING : c. 1834			
ORIGINAL USE : Residence			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 2,4			
DESCRIPTION : 1½ storey centre gable gray stucco with cobblestone accents flat eaves support date of 1834			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social and Cultural Impact Study, May 1984	
		PRESENT OWNER G. Ferguson	


NAME : Farm House		REFERENCE NO : B.3	
NATURE OF FEATURE : Farm House		DATE OF REPORT : November 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 3444 Trafalgar Road, Oakville, Ontario		
	LOT 13	CON 1 NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/5		
	MILITARY GRID REF. 023168		
AIR PHOTO REF.			
DATING : c. 1867			
ORIGINAL USE : Farm House			
CURRENT USE : Farm House			
OWNERSHIP : Private			
PROTECTION STATUS : 2,4			
DESCRIPTION : 1½ storey centre gable, Ontario gothic originally 10" thick stone construction, now stuccoed original windows remnant farmstead plantings			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social and Cultural Impact Study, May 1984 Town of Oakville LACAC	
		PRESENT OWNER Mr. J. Bentley	

NAME : House		REFERENCE NO : B.4	
NATURE OF FEATURE : House		DATE OF REPORT November 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 3558 Trafalgar Road, Oakville, Ontario		
	LOT 13	CON	1NDS
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30M/5		
	MILITARY GRID REF. 020170		
	AIR PHOTO REF.		
			
DATING : c. 1900			
ORIGINAL USE : Barn			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 4			
DESCRIPTION : 1½ storey, part wood and part aluminum siding with 7 feet of rough blocks Farmstead and plantings , no longer exist			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social and Cultural Impact Study May 1984	
		PRESENT OWNER Mr. W Watson	

NAME : House		REFERENCE N° : B.5	
NATURE OF FEATURE : House		DATE OF REPORT : November 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 3369 Sixth Line RR#1, Oakville, Ontario L6J 4Z2		
	LOT 16	CON 1NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30M/5		
	MILITARY GRID REF. 018157		
		AIR PHOTO REF.	
DATING : 1862			
ORIGINAL USE : Farm House			
CURRENT USE : Farm House			
OWNERSHIP : Private			
PROTECTION STATUS : 2&4			
DESCRIPTION : 1½ Storey, Polychrome brick, porch added Gable window altered Remnant farmstead plantings c. 1920			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Trafalgar Township Assessment Halton County Atlas - 1977 Social & Cultural Impact Study, May 1984 Town of Oakville, LACAC	
		PRESENT OWNER	



NAME : Residence		REFERENCE NO : B.6	
NATURE OF FEATURE : Residence		DATE OF REPORT : November 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 257 Dundas Street East, R.R #1, Oakville, Ontario		
	LOT 13	CON 1 NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/5		
	MILITARY GRID REF. 033155		
	AIR PHOTO REF.		
DATING : 1850's			
ORIGINAL USE : Farm Residence			
CURRENT USE : Farm Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 2,4			
DESCRIPTION : 1½ storey centre gable, white stucco over brick Ontario gothic style with transom and side lights French-style windows at front			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS	
		Social and Cultural Impact Study, May 1984	
		Town of Oakville LACAC	
		The Governor's Road, Byers & McBurney	
Trafalgar Township Assessment Rolls		Halton County Atlas	
		PRESENT OWNER Patrick & Anne Brophy	


NAME : House		REFERENCE NO : C.1	
NATURE OF FEATURE : House		DATE OF REPORT : November, 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 3371 Trafalgar Road, Oakville, Ontario		
	LOT 12	CON 1NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30M/5		
	MILITARY GRID REF. 026167		
	AIR PHOTO REF.		
DATING : 1868			
ORIGINAL USE : Farm House			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 4			
DESCRIPTION : - House built in 1868 - A 1½ storey gable house of clapboard construction.			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS :Social & Cultural Impact Study, May 1984 :Town of Oakville, LACAC	
		PRESENT OWNER V & N Shaparew	

NAME : House		REFERENCE N° : C.2	
NATURE OF FEATURE :		DATE OF REPORT : November, 1984	
House		THEME CATEGORY :	
LOCATION	ADDRESS : 3437 Trafalgar Road, Oakville, Ontario.		
	LOT 12	CON INDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/5		
	MILITARY GRID REF. 024169		
	AIR PHOTO REF.		
DATING : c. 1877			
ORIGINAL USE : Farm House			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 4			
DESCRIPTION : - Built c. 1877 (Tremain's map) - A 1½ double gable house - Originally wood frame, but now stucco - Remnants of farmstead plantings - Original barn			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social & Cultural Impact Study, May/84	
		PRESENT OWNER I & A Posa	


NAME : House		REFERENCE NO : C.3	
NATURE OF FEATURE : House		DATE OF REPORT: November, 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 3555 Trafalgar Road, Oakville, Ontario		
	LOT 12	CON 1NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30M/12		
	MILITARY GRID REF. 021171		
	AIR PHOTO REF.		
DATING : c. 1868			
ORIGINAL USE :			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 4			
DESCRIPTION : - A 1½ central gable, early Ontario farm house - Wood frame and stucco - Much altered over the years			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS	
		: Social & Cultural Impact Study, May 1984 : Town of Oakville. LACAC	
		PRESENT OWNER	
		J & K Melanson	

NAME : Farm House		REFERENCE NO : C.4	
NATURE OF FEATURE : Farm House		DATE OF REPORT : November, 1984	
		THEME CATEGORY : S-European	
LOCATION	ADDRESS : 1086 Burnhamthorpe Road, East, Oakville, Ontario.		
	LOT 10	CON 1 NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30M/12		
	MILITARY GRID REF. 028179		
AIR PHOTO REF.			
DATING : 1839			
ORIGINAL USE : Farm House			
CURRENT USE : Farm House			
OWNERSHIP : Private			
PROTECTION STATUS : 2, 4			
DESCRIPTION : - Polychrome, Centre Gable, Palladian Plan House. - Rear built C. 1824 - Bricks made on site, in a kiln made by the builder. - A 3 pt. well made of imported thin English Brick in 1824 - Original barns on site - W. S. Bowbeer built the main house. He was a Landscape Gardener, he laid out the garden, a "Black Ash Swamp" with a famous spring located on the property.			
		CRITERIA 3	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS	
		Local Architectural Conservatory Authority Records	
		Social & Cultural Impact Study, May 1984	
		Oakville Heritage Community Study - Inventory 1976-1981	
		Ontario Inventory of Building	
		PRESENT OWNER Leo & Sybil Rampen	

NAME : House		REFERENCE NO : C.5	
NATURE OF FEATURE : House		DATE OF REPORT : November, 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 1158 Burnhamthorpe Road E., Oakville, Ont., L6J 4Z2		
	LOT 9	CON 1NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30M/12		
	MILITARY GRID REF. 029182		
	AIR PHOTO REF.		
			
DATING : 1868			
ORIGINAL USE : Farm House			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 4			
DESCRIPTION : - Red brick with side veranda - Original beams, pine flooring - Original barns on property - Remnant farm plantings along laneway			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS : Social & Cultural Impact Study, May 1984 . Town of Oakville, LACAC	
		PRESENT OWNER Vera Dryland	



NAME : House		REFERENCE NO : C.6	
NATURE OF FEATURE : House		DATE OF REPORT : November 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 1264 Burnhamthorpe Rd.E., RR#1, Oakville Ont.,		
	LOT 8	CON 1NDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30M/12		
	MILITARY GRID REF. 032184		
	AIR PHOTO REF.		
DATING : c.1850			
ORIGINAL USE : Farm House			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 4			
DESCRIPTION : - 1½ Storey, center gable - Ontario Gothic - Remnant farm plantings - New siding			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social & Cultural Impact Study, May 1984	
		PRESENT OWNER	

NAME : House		REFERENCE NO : C.7	
NATURE OF FEATURE :		DATE OF REPORT : November 1984	
School		THEME CATEGORY :	
LOCATION	ADDRESS : 1536 Burnhamthorpe Road East, R.R.#1, Oakville, Ont.		
	LOT 6	CON	INDS
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/12		
	MILITARY GRID REF 039193		
AIR PHOTO REF.			
DATING : 1874			
ORIGINAL USE : School			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS: 4			
DESCRIPTION :			
- Built in 1874 - White aluminum siding over original wood siding - Gothic window - Renovated from a school house to a residence			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Halton County Registry Office Oakville Library Access Photographs from former teachers and pupils Social & Cultural Impact Study, May 1984	
		PRESENT OWNER W. & J. Sparling	

NAME : House		REFERENCE NO : C.8	
NATURE OF FEATURE : Farm House		DATE OF REPORT : November, 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : 3480 Ninth Line, R. R. #1, Oakville, Ontario		
	LOT 6	CON INDS	
	AM Oakville		
	RM Halton		
	1:50 000 MAP REF. 30 M/12		
	MILITARY GRID REF. 039191		
	AIR PHOTO REF.		
DATING : 1886			
ORIGINAL USE : Farm House			
CURRENT USE : Residence			
OWNERSHIP : Private			
PROTECTION STATUS : 4			
DESCRIPTION : - 1½ storey, red & yellow brick polychrome, Victorian style - Exterior alterations, i.e. porch - Built 1886 - Remnant farm plantings & out buildings			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS Social & Cultural Impact Study, May, 1984 Halton County Registry Office Town of Oakville, LACAC	
		PRESENT OWNER Florence Brown	


NAME : Hunterbrook Farm		REFERENCE NO : D.1	
NATURE OF FEATURE : Residence		DATE OF REPORT: November 1984	
		THEME CATEGORY:	
LOCATION	ADDRESS : Bronte Road, First Line, Milton, Ontario		
	LOT 5	CON 2	
	AM Milton		
	RM Halton		
	1:50 000 MAP REF. 30 M/5		
	MILITARY GRID REF. 935142		
	AIR PHOTO REF.		
DATING : c. 1830			
ORIGINAL USE : Farm Residence			
CURRENT USE : Farm Residence			
OWNERSHIP : Private			
PROTECTION STATUS: 2			
DESCRIPTION : Early Ontario farmhouse 2 storey barns			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS	
		PRESENT OWNER	

NAME : Farm Residence		REFERENCE NO : D.2	
NATURE OF FEATURE : Farm Residence		DATE OF REPORT: November 1984	
		THEME CATEGORY:	
LOCATION	ADDRESS : 5357 Bronte Road, Milton, Ontario		
	LOT 3	CON 2	
	AM Milton		
	RM Halton		
	1:50 000 MAP REF. 30 M/5		
	MILITARY GRID REF. 946131		
	AIR PHOTO REF.		
DATING : c. 1880			
ORIGINAL USE : Farm Residence			
CURRENT USE : Farm Residence			
OWNERSHIP : Private			
PROTECTION STATUS: 2			
DESCRIPTION : 1½ storey centre gable, Ontario gothic stone foundation, stucco finish remnant farmstead plantings in excellent condition original barns and outbuildings			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS	
		PRESENT OWNER	
		Clare F. Ford	


NAME : House		REFERENCE N° : E.1	
NATURE OF FEATURE : House		DATE OF REPORT : November 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : Tremaine Road, Milton , Ontario		
	LOT 8	CON	7
	AM Milton		
	RM Halton		
	1:50 000 MAP REF. 30M/5		
	MILITARY GRID REF. 913141		
	AIR PHOTO REF.		
			
DATING : c. 1850			
ORIGINAL USE : Farm House			
CURRENT USE : Farm House			
OWNERSHIP : Private			
PROTECTION STATUS : 2			
DESCRIPTION : Five bay, 1½ storey, central gable Porch later addition Early Ontario farmhouse			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS	
		PRESENT OWNER	

NAME : House		REFERENCE N° : E.2	
NATURE OF FEATURE : Farm House		DATE OF REPORT : November 1984	
		THEME CATEGORY :	
LOCATION	ADDRESS : Tremaine Road, Milton, Ontario		
	LOT 6	CON 7	
	AM Milton		
	RM Halton		
	1:50 000 MAP REF. 30M/5		
	MILITARY GRID REF. 921133		
	AIR PHOTO REF.		
DATING : c. 1870			
ORIGINAL USE : Farm House			
CURRENT USE : Farm House			
OWNERSHIP : Private			
PROTECTION STATUS : 2			
DESCRIPTION : Century Farm Brick, 2 storey, painted white, bay window Original porch Verge board intact			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS	
		PRESENT OWNER	

NAME : House		REFERENCE No : E.3	
NATURE OF FEATURE : House		DATE OF REPORT: November 1984	
		THEME CATEGORY:	
LOCATION	ADDRESS : Bell School Line, Milton, Ontario		
	LOT 6	CON 7	
	AM Milton		
	RM Halton		
	1:50 000 MAP REF. 30M/5		
	MILITARY GRID REF. 915122		
	AIR PHOTO REF.		
DATING : c. 1890			
ORIGINAL USE : Farm House			
CURRENT USE : Farm House			
OWNERSHIP : Private			
PROTECTION STATUS: 2			
DESCRIPTION : - Brick 2 storey, stone lintels & sills - Remnant early farmstead plantings - Renovations to facade			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS	
		PRESENT OWNER	



NAME : House		REFERENCE NO : E.4	
NATURE OF FEATURE : House		DATE OF REPORT: November 1984	
		THEME CATEGORY:	
LOCATION	ADDRESS : Tremaine Road, Milton Ontario		
	LOT 9	CON 7	
	AM Milton		
	RM Halton		
	1:50 000 MAP REF. 30M/5		
	MILITARY GRID REF. 909145		
	AIR PHOTO REF.		
DATING : c. 1900			
ORIGINAL USE : Farm House			
CURRENT USE : Farm House			
OWNERSHIP : Private			
PROTECTION STATUS: 2			
DESCRIPTION : 2 storey brick, stone block foundation Remnant plantings			
		CRITERIA	
		PRINTED MANUSCRIPT OR PHOTOGRAPHIC RECORDS	
		PRESENT OWNER	



APPENDIX C
CORRESPONDENCE WITH LACACS

November 12, 1984.

Mr. Don Hayward,
L.A.C.A.C. Chairman,
Town of Milton,
c/o Town Clerk,
P.O. Box 1005,
251 Main St. East,
MILTON, Ontario.
L9T 5B6

Dear Mr. Hayward:

RE: HALTON HERITAGE STUDY FOR SOLID WASTE MANAGEMENT SITE
SELECTION - HALTON REGION
OUR FILE G84029-HR01

Per our conversation today, Landplan is conducting an inventory and analysis of the heritage features located on the six candidate sites for use in the Solid Waste Management Site Selection for Halton Region.

Our work involves the review of the existing documents on the heritage features of the study area (Halton Heritage Study, 1981, and Social and Cultural Impact Study, C.R.O.W., 1984) in addition to field study.

We have enclosed maps of sites "D" & "E" which is located in the Town of Milton. Your input in the form of an updated inventory on the heritage features of sites "D & E" would be of valuable assistance in assuring the completeness of our study.

If you have any questions please call.

Yours very truly,

THE LANDPLAN COLLABORATIVE LTD.,

Earl J. Perry.
EJP/cb.

c.c. to: Joan Bidell

the
landplan
collaborative limited

landscape architecture
land planning

128 Woolwich Street
Guelph, Ontario
N1H 3V2
(519) 824-8664



RECEIVED 27 NOV

Milton - LOCAL ARCHITECTURAL CONSERVATION ADVISORY COMMITTEE

RECEIVED

December 21, 1984

WALKER & HARTMAN
ASSOCIATES LIMITED

The Landplan Collaborative
Limited
128 Woolwich Street
GUELPH, Ontario
N1H 3V2

Attention: Mr. Earl J. Perry

Dear Sir:

Re: Halton Heritage Study For
Solid Waste Management Site
Selection - Halton Region
(Your File - G84029-HR01)

This letter is with respect to the letter which you sent to the L.A.C.A.C. on November 12th, 1984. Please be advised that we are in the process of researching the six candidate sites for use in the Solid Waste Management Site Selection in Halton Region dealing with the analysis of heritage features only.

We will notify you of the results once the information has been obtained.

We thank you for your interest in the Halton Region area, and will be in touch with you soon.

Sincerely,

Don Hayward,
Chairman,
L.A.C.A.C.

DH/an

the

landplan

collaborative limited

landscape architecture
land planning

128 Woolwich Street
Guelph, Ontario
N1H 3V2
(519) 824-8664

November 12, 1984.

Mr. David Nelson,
LACAC Secretary,
Town of Oakville,
c/o Planning Department,
P.O. Box 310,
OAKVILLE, Ontario.
L6S 5A6

Dear Mr. Nelson:

RE: HALTON HERITAGE STUDY FOR USE IN SOLID WASTE MANAGEMENT
SITE SELECTION - HALTON REGION
OUR FILE NO: G84029-HR01

Per our conversation today, Landplan is conducting an inventory and analysis of the heritage features located on the six candidate sites for use in the Solid Waste Management Site Selection for Halton Region.

Our work involves the review of the existing documents on the heritage features of the study area (Halton Heritage Study, 1981, and Social and Cultural Impact Study, C.R.O.W., 1984) in addition to field study.

We have enclosed maps of sites "A, B, & C" which are located in the Town of Oakville. Your input in the form of an updated inventory on the heritage features of sites "A, B & C" would be of valuable assistance in assuring the completeness of our study.

If you have any questions, please call.

Yours very truly,

THE LANDPLAN COLLABORATIVE LTD.,

Earl J. Perry.
EJP/cb.

c.c. to: Joan Bidell



THE CORPORATION OF THE TOWN OF OAKVILLE

TELEPHONE 845-6601

P.O. BOX 310
L6J 5A6

November 22, 1984.

Mr. Earl J. Perry
The Land Plan Colloborative Ltd.
128 Woolwich Street
Guelph, Ontario
N1H 3V2

Dear Mr. Perry:

Re: Halton Heritage Study for use in
Solid Waste Management Site Selection
Your File: (G 84029-HR01)

Returned herewith is the plan you forwarded to me. I have noted those buildings of interest to LACAC on the drawing. Locations are only approximate as our house numbering plans do not cover this area. I have provided the municipal address from the file to assist you.

The locations in red are of primary interest to Oakville LACAC; this colour denotes those buildings which should be designated under the Ontario Heritage Act, Part IV. The locations in green denote those buildings which will be reviewed in depth once all the primary locations in the Town of Oakville have been dealt with.

Should you desire additional information on Heritage Resources in general or for the sites noted in particular, please feel free to contact me.

Yours truly,

D. Nelson,
LACAC Secretary

DN:cw

November 12, 1984.

Mr. John Williams,
LACAC Chairman,
City of Burlington,
c/o City Clerk,
426 Brant Street,
BURLINGTON, Ontario.
L7R 3Z6

Dear Mr. Williams:

RE: HALTON HERITAGE STUDY FOR SOLID WASTE MANAGEMENT
SITE SELECTION - HALTON REGION
OUR FILE: G34029-HR01

Per our conversation today, Landplan is conducting an inventory and analysis of the heritage features located on the six candidate sites for use in the Solid Waste Management Site Selection for Halton Region.

Our work involves the review of the existing documents on the heritage features of the study area (Halton Heritage Study, 1981, and Social And Cultural Impact Study, CROW., 1984), in addition to field study.

We have enclosed a map of site 'F' which is located in the City of Burlington. Your input in the form of an updated inventory on the heritage features of Site 'F' would be of valuable assistance in assuring the completeness of our study.

If you have any questions, please call.

Yours very truly,

THE LANDPLAN COLLABORATIVE LTD.,

Earl J. Perry,
EJP/cb.

c.c. to: Joan Bidell

the
landplan
collaborative limited

landscape architecture
land planning

128 Woolwich Street
Guelph, Ontario
N1H 1V2
(519) 824-8664